

**SURVEY &
REMONUMENTATION**

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	D-13, S $\frac{1}{4}$ corner Section 32 Spring Lake Twp
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

RECORDED

95 NOV 29 PM 1:33

Elizabeth Coleman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas E. Joiner, in a field survey on 11/7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837.	Liber 2, Page 39	02-16-73	Set Cast Iron Monument
Post Set By Calvin Britain, D.S.	Found "T" Iron		16" Oak SW 26.48
N 30°E 14 6" Beech	24" Oak NNE	22.70	Tw. Ash SE 21.81
N 64°W 26 7" Beech	Power Pole WSW	30.37	24" Oak N 23.72
	18" Oak W	34.54	Power Pole WSW 30.41
	18" Oak SW	25.85	N $\frac{1}{4}$ corner W 75.00
	Sec. 5-7-17 W	75.00	Sect. 5
	Corner 15		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 4, Page 227

16" Oak	SW	26.48
Tw. Ash	SE	21.81
24" Oak	N	23.72
Power Pole	WSW	30.41
N $\frac{1}{4}$ cor., Sec.5	W	75.00


P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Robert D. McDowell
YOM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in NE side	18" Oak	AZ	298°	39.87
O.C. Remon Tag & Nail in N side	18" Oak	AZ	270°	35.44
O.C. Remon Tag & Nail in E side	14" Maple	AZ	188°	20.12
O.C. Remon Tag & Nail in N side	7" Beech	AZ	74°	16.23
N $\frac{1}{4}$ corner of Section 5		AZ	270°	75.00



Signed by Thomas E. Joiner
Surveyor's Michigan License No. 18435

Date 11-16-95