

**SURVEY &
REMONUMENTATION**

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:46

COMMISSION

For corners in
OTTAWA
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------------|
| 1. Public Land Survey | T 8N R 16W | E-4, W 1/2 Corner |
| | T _____ R _____ | Section 9 |
| | T _____ R _____ | Spring Lake Twp. |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Deborah S. Johnson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, THOMAS E. JOINER in a field survey on 11-21-, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
04-01-1837 Liber 1, Pg. 639, 10-13-72
Post set by John Mullet, D.S. Set Cast Iron Monument
S61°W 26 30" Hemlock W. 15.64 30" Twin Birch
N27°E 7 6" Hemlock N. 28.45 28" Maple
S. 6.32 28" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 1, Pg. 639, 10-13-72
West 15.64 30" Twin Birch (stump)
North 28.45 28" Maple
South 6.32 28" Maple

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Harold P. Hedewald



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in South side Twin 10" Oak	Az. 118°	17.35
O.C. Remon Tag & Nail in W side 38" Maple	Az. 180°	7.57
O.C. Remon Tag & Nail in S side 44" Oak	Az. 270°	38.42
O.C. Remon Tag & Nail in E side 24" Maple	Az. 328°	28.94

Signed by Thomas E. Joiner Date 12-9-94
Surveyor's Michigan License No. 18435