

SURVEY & REMONUMENTATION

FEB 27 1998

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Ottawa _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T8N R16W	E-8 (E 1/4 cor. Sec. 20)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

97 DEC -8 AM 11:31

Gary Sublett
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Steve Lampen _____, in a field survey on November 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		
3												
4		7		8		9		10		11		
5												
6		18		17		16		15		14		1
7												
8		19		20		21		22		23		2
9												
10		30		29		28		27		26		2
11												
12		31		32		33		34		35		3
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-8 G.L.O.
1832 Britian
40.00' set 1/2 mile post
8" Beech S 25 W 7
16" Beech N 30 E 17

This position fits the monumentation of Boltwood Addition, Liber 1, Page 66, 1868, Akeley's Addition Plat Book 1, Pages 58 through 60, 1867. Monroe and Harris Addition - 1867, monument map of City of Grand Haven by Brayton - 1876

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8
Found railroad spike in railroad tie

This position fits the monumentation of Boltwood Addition, Liber 1, Page 66, 1868, Akeley's Addition Plat Book 1, Pages 58 through 60, 1867. Monroe and Harris Addition - 1867, monument map of City of Grand Haven by Brayton - 1876

Replaced railroad spike with Ottawa County Remonumentation iron and cap and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-1-97

YDT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8
Set Ottawa County Remonumentation iron and cap
AZ = Michigan State Plane grid direction

Remonumentation tag North side power pole	250° 34'	31.28'
Remonumentation tag North side power pole	104° 21'	37.42'
Centerline main line CSX rails	70°	0.46'
U.S.C. & G.S. B.M. M-25	348° 28'	441.41'
Northwest corner house foundation	179° 49'	169.91'
Old fence corner = on East West 1/4 line	88° 47'	66.00'
Hydrant top centerline	359° 36'	140.98'
Remonumentation tag North side power pole	305° 08'	75.65'

This position of E-8 fits the monumentation of Boltwoods Addition and Akeley's Addition

Signed by Steven Lampen Date DECEMBER 1, 1997

Surveyor's Michigan License No. 37279

