

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:46

Deborah R. Coleman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
OTTAWA

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	E-13, SW Corner
	T _____ R _____	Section 33
	T _____ R _____	Spring Lake Twp.
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, THOMAS E. JOINER in a field survey on 11-22- 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837	Liber 1, Pg. 775, 12-04-72
Corner set by Calvin Britain, D.S.	Cast Iron Monument
12" Beech is post	SW 16.05 12" Cherry
	NE 20.42 8" Cherry
	NW 3.67 6" Pine
	W. 75.26 Grand Haven Twp. Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 1, Pg. 775, 12-04-72
SW 16.05 12" Cherry
West 75.26 Grand Haven Township corner

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Maday D. Hedecore



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument		
SE corner. conc. Block Foundation House #14407	AZ.	30° 22.17
O.C. Remon Tag & Nail in SW Side 9" Scotch Pine	AZ.	120° 6.66
O.C. Remon Tag & Nail in NW side Twin 12" Cherry	AZ.	230° 16.38
O.C. Remon Tag & Nail in S side 6" Oak	AZ.	250° 36.11
Cast Iron Monument, Grand Haven Twp cor. E-1	AZ.	270° 75.10
Split Rail Wood Fence 0.3' South of corner		

Signed by Thomas E. Joiner Date 12-9-94
Surveyor's Michigan License No. 18435