

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:46

Dorothy Ballman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

OTTAWA <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	<u>F-5, S$\frac{1}{2}$ Corner</u> <u>Section 9</u> <u>Spring Lake Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS E. JOINER in a field survey on 11-21-, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:
04-01-1837 Liber 5, Pg. 276, 08-17-87
Post set by John Mullet, D.S. Set Cast Iron Monument
N68°W 07 15" Hemlock NW 61.51 Power Pole
S32°E 19 6" Hemlock NW 44.61 Power Pole
SW 31.20 Telephone Pole
SE 54.25 Twin 8" Oak
E. 5.79 $\frac{1}{4}$ Track

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 5, Pg. 276, 08-17-87
NW 44.61 Power Pole
SW 31.20 Telephone Pole
E 5.79 $\frac{1}{4}$ Track

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Wesley D. Peterson



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in S side 14" Oak	Az. 65°	57.09
O.C. Remon Tag & Nail in N side 6" Oak	Az. 142°	61.45
O.C. Remon Tag & Nail in N Side 11" Poplar	Az. 244°	68.72
O.C. Remon Tag & Nail in E side Twin 8" Maple	Az. 328°	68.41
$\frac{1}{4}$ West Rail of RR Tracks	Az. 90°	3.52

Signed by Thomas E. Joiner Date 12-9-94
Surveyor's Michigan License No. 18435