

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 MAY -5 AM 10:55

For corners in

OTTAWA <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	<u>G-4, E½ Corner</u>
	T _____ R _____	<u>Section 9</u>
	T _____ R _____	<u>Spring Lake Twp</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Reginald Kullman*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, THOMAS E. JOINER in a field survey on APRIL 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

03-30-1837	Liber 1, Pg. 777, 12-04-72
Post set by John Mullet	Liber 5, Pg. 330, 08-09-88
West 36 12" Hemlock	Set Cast Iron Monument
N77°E 15 8" Hemlock	SSE 109.54 Power Pole
	NE 52.94 Ⓢ Fire Hydrant
	NW 58.85 Power Pole
	SW 57.23 Guy Pole

**SURVEY &  
 REMONUMENTATION**  
 OCT 24 1994  
 COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

NE 52.94 Ⓢ Fire Hydrant  
 NW 58.85 Power Pole  
 SW 57.23 Guy Pole



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument in Monument Box	
Ⓢ Bolt Top Fire Hydrant	Az. 32°36' 52.98
O.C. Remon. Tag & Nail in West Side Power Pole	Az. 164°17' 109.71
O.C. Remon. Tag & Nail in NE Side Power Pole	Az. 304°04' 58.84
O.C. Remon. Tag & Nail in NW Side Guy Pole	Az. 238°28' 57.03

OTTAWA COUNTY  
 DEED APPROVED 4/10/94  
*Ardozo P. Velazquez*  
 Date 4-15-94

Signed by Thomas E. Joiner  
 Surveyor's Michigan License No. 18435