

SURVEY & REMONUMENTATION

OCT 24 1994

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 MAY -6 AM 10:55

Phyllis Coleman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

OTTAWA (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	G-5, SE Corner
	T _____ R _____	Section 9
	T _____ R _____	Spring Lake Twp.
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●						
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, THOMAS E. JOINER, in a field survey on APRIL 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

03-30-1837	Liber 5, Pg. 34, 03-04-83
Post set by John Mullet, D.S.	Set Cast Iron Monument in Monument Box
N10°W 22 15" Beech	NW 40.47 Nail & Washer SE Side Telephone Pole
S62°E 10 8" Beech	NE 54.72 Ⓞ Top Hydrant
	SE 45.39 P.K. NE Side Power Pole
	SW 76.42 P.K. East Side Twin 20" Willow

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron MONument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

NW 40.47 Nail & Washer in SE Side Telephone Pole
 NE 54.72 Ⓞ Top Hydrant
 SE 45.39 P.K. NE Side Power Pole
 SW 76.42 P.K. East Side Twin 20" Willow



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument in Monument Box		
Ⓞ Top Bolt Fire Hydrant	Az. 28°37'	54.74
O.C. Remon. Tag & Nail in NW Side Power Pole	Az. 126°42'	44.76
O.C. Remon. Tag & Nail in East Side Twin 20" Willow	Az. 203°57'	77.53
O.C. Remon. Tag & Nail in NE Side Power Pole	Az. 321°13'	40.83

Signed by Thomas E. Joiner
 Surveyor's Michigan License No. 18435

OTTAWA COUNTY
 PEER APPROVED
Stephen P. McDowell
 Date 4-15-94