

OTTAWA COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 18 PM 4: 55

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8</u> R <u>16</u>	G-7, SE corner
	T _____ R _____	Section 16
	T _____ R _____	Spring Lake Twp
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Richard Holman*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, THOMAS E. JOINER in a field survey on Nov. 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-7  
 John Mullett D.S. 1832  
 North between Sections 21 & 22  
 80.00 chains corner of Sections  
 16, 15, 21, 22 in river.  
 4.80 chains East set meander post  
 and 2.40 chains North over river set  
 meander post in Marsh on right bank.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 falls 80± feet South of the North bank of the Grand River in the water. Established G-7 according to the Plat of Barbers Addition in Liber 3, Page 576; And John Kistler & Associates, Inc., Job #3025, #8911. Set witness monument 155.00 feet North on the East line Section 16 at centerline of School Street and centerline of vacated River Street (set O.C. Remon. Cap over 2 foot long steel bar in monument box). Set witness monument 155.00 feet East on South line Section 15 (set O.C. Remon. Cap over 3 foot long steel bar). See drawing on back.

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12-9-96

*G.P.M.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 N. Set 2 foot steel bar & Ottawa County Remon. Cap in Monument Box.		
Ottawa County Remon tag and nail in SE side 11" Ash	AZ 240°	Dist 19.30
Ottawa County Remon tag and nail in E side 6" Beech	AZ 175°	Dist 34.10
Ottawa County Remon tag and nail in N side 8" Beech	AZ 100°	Dist 61.38
Ottawa County Remon tag and nail in W side 9" Ash	AZ 15°	Dist 76.91
G-7 E. Set 3 foot steel bar & Ottawa County Remon. Cap		
Ottawa County Remon tag and nail in S side 10" Elm	AZ 83°	Dist 79.83
Ottawa County Remon tag and nail in SW side side 22" Willow	AZ 120°	Dist 110.35
Ottawa County Remon tag and nail in W side 6" Maple	AZ 164°	Dist 75.20
Ottawa County Remon tag and nail in S side Twin 14" Catalpa	AZ 295°	Dist 46.01

Signed by Thomas E. Joiner Date 12-6-96  
 Surveyor's Michigan License No. 18435

