SURVEY & REMONUMENTATION

APR 2 4 1995

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 15 AMII: 45

COMMISSION OTTAWA		Filing Requi	QLIBELIS AND	
		Located In:	Corner Code =##	REGISTER OF DEEDS OTTAWA COUNTY. MI
1.	Public Land Survey	T 8N R 16W T R R T R R	G-9, SE Corner Section 21 Spring Lake Twp.	
2.	Property Controlling in Section	S T R S T R		
3.	Miscellaneous Property in Sec.	S T R S T R		Register of Deeds Stamp & File Number

I, THOMAS E. VOINEX in a field survey on _ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

___ , Recorded Plat _

10 11 12

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: 05-27-1832 Liber 5,Pg. 262,01-16-87

Post set by John Mullet

5. Private Claims

N73°E 20 18" Hemlock

S20°W 8 15" Hemlock

Ottawa County Cast Iron Monument

NNW 90.65 SE Corner Foundation

NW 75.41 Corner brick building face

WSW 75.66 Corner brick building face

SW 77.26 PK NE side of power pole

SE 49.02 PK NE side of power pole

44.45 € Top of Hydrant NE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 5, Pg. 262, 01-16-87 NNW 90.65 SE Cor. Foundation NW 75.41 Cor. Brick Bld. Face Cor. Brick Bld. Face WSW 75.66 SW 77.26 PK NE side of Power Pole 49.02 PK NE side of Power Pole SE NE 44.45 G. Top of Hydrant

P.A. 345 OTTAWA COUNTY PEER APPROVED_

THOMAS E. JOINER LAND SURVEYOR 18435

Land St

REVISED MAY 14, 1975 REVISED JAN., 1983

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Fron Monument in Monument Box

C Top Operating Nut on Hydrant	Az.	64°	44.46
O.C. Remon Tag & Nail in NE side Guy Pole	Az.	138°	49.02
NE Cor. Brick Bdg. #1454	Az.	213°	77.20
O.C. Remon Tag & Nail in N side 42" Maple	Az.	260°	98.79
O.C. Remon Tag & Nail in NE side Power Pole	Az.	332°	38.77

Signed by Homas	C. 4	7 min	Date	12-9-94	
Surveyor's Michigan License No.		18435		THE SERVICE OF THE STATE PART OF LAW SHOWEVERS 188 25	111