

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:45

Phyllis Hollman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
OTTAWA

Located In: Corner Code #

(County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 16W	I-11, NE Corner Section 34 Spring Lake Twp.
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, THOMAS E. JOINER, in a field survey on 11-21-, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

05-26-1832 Liber 2, Pg. 503, 08-09-74
Post set by John Mullet, D.S. Set Cast Iron Monument in place of Iron Pipe
S26°E 36 12" Pine SW 44.98 Guy Pole
N68°W 15 14" Pine NW 60.07 Power Pole
NE 43.06 Telephone Pole
SE 30.55 Street Sign
NW 101.03 SE Corner brick house

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 2, Pg. 503, 08-09-74
NW 60.07 Power Pole
NW 101.03 SE Corner Brick House

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Robert D. Medewald

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument in Monument Box

Q. Top operating Nut on Hydrant	Az. 25°	46.00
O.C. Remon Tag & Nail in NW side 24" Maple	Az. 252°	94.51
SE Cor. Brick Entrance House #15213	Az. 312°	105.55
O.C. Remon Tag & Nail in NE side 16" Maple	Az. 326°	73.20



Signed by Thomas E. Joiner Date 12-9-94
Surveyor's Michigan License No. 18435