

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:45

COMMISSION

For corners in

Ottawa <small>(County)</small>	Located In:	Corner Code ##	
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	K-2, W $\frac{1}{2}$ Cor.	
	T _____ R _____	Section 1	
	T _____ R _____	Spring Lake Twp.	
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Deborah Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, THOMAS E. JOINER in a field survey on 11-27-94, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

03-29-1837	Liber 4, Pg. 8, 12-11-79	Liber 1, Pg. 109, 10-07-71
Post Set by John Mullet, D.S.	Found Cast Iron Monument	SW 65.72 Nail in face of 24" White Pine
N 75°E 32 14" White Oak	West 6.09 28" Oak	SE 20.32 Nail in face of 24" White Pine
N 26°W 63 36" Pine	North 67.67 Power Pole	NE 66.69 Nail in face of 20" White Pine
	SE 15.48 14" Oak	North 67.35 Nail in face of P.P.
		North 74.25 4" Tile

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument and accepted as a careful and faithful perpetuation of the position of the original corner.


Liber 4, Pg. 8, 12-11-79	Liber 1, Pg. 109, 10-07-71	
West 6.09 28" Oak	SW 65.72 Nail in face of 24" White Pine	
North 67.67 Power Pole	SE 20.32 Nail in face of 24" White Pine	
	North 67.35 Nail in face of P.P.	

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Robert D. Medewald

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon. Tag & Nail in W side 14" Oak	Az. 156° 29.32
O.C. Remon. Tag & Nail in E side 20" Oak	Az. 204° 35.72
O.C. Remon. Tag & Nail in NW side 15" Oak	Az. 228° 14.07
O.C. Remon. Tag & Nail in N side 27" Oak	Az. 285° 6.20
South edge of asphalt of Hickory Street	Az. 00° 23±



Signed by Thomas E. Joiner Date 12-12-94
Surveyor's Michigan License No. 18435

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983