

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 MAY -6 AM 10:55

Phyllis Williams
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	<u>K-8 E¹ Corner</u>
	T _____ R _____	<u>Section 23</u>
	T _____ R _____	<u>Spring Lake Twp</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, THOMAS E. JOINER in a field survey on APRIL 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 03-27-1837 Liber 1, Pg. 91
 Post set by John Mullett Liber 4, Pg. 296 01-29-82
 S01°E 27 8" Beech Liber 5, Pg. 37, 03-04-83
 S78°W 32 7" Beech Cast Iron Monument
 S60°W 63.61 Nail & Washer in NE Side 20" Oak
 N80°E 29.01 Nail & Cap in W. Side P.P.
 S45°E 106.84 NW Corner Conc. Block Fnd. to House


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found cast iron monument and accepted as a careful and faithful perpetuation of the position of the original corner.

S60°W 63.61 Nail & washer in NE side 20" Oak
 N80°E 29.01 Nail & tag in West side power pole

SURVEY &
 REMONUMENTATION

OCT 24 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument
 O.C. Remon. Tag & Nail in S. Side Power Pole Az. 80°00' 29.18
 O.C. Remon. Tag & Nail in E. Side Power Pole Az. 340°00' 49.94
 O.C. Remon. Tag & Nail in S. Side 24" Oak Az. 250°00' 64.98
 O.C. Remon. Tag & Nail in N. Side 30" Oak Az. 140°00' 53.47

4/18/94
George P. DeWald

Signed by Thomas E. Joiner
 Surveyor's Michigan License No. 18435

Date 4-15-94