

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:46

Thomas E. Joiner
REGISTER OF DEEDS
OTTAWA COUNTY, MI
**SURVEY &
REMONUMENTATION**

DEC 05 2000

SECTION
Register of Deeds Stamp & File Number

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	L-3, S $\frac{1}{2}$ Cor. Section 1 Spring Lake Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, THOMAS E. JOINER in a field survey on 11-21- 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

03-28-1837
Post Set by John Mullet, D.S.
N 09°E 32 16" W. Oak
S 30°W 11 18" W. Oak

Liber 4, Pg. 7, 11-30-79
Found Steel Bar
East 29.69 Power Pole
SE 83.26 6" Catalpa
WNW 42.51 9" Poplar
WNW 47.84 13" Poplar
NNW 74.46 6" Metal Guard Post (face)

Liber 1, Pg. 81, 09-24-71
Found Iron Bar
East 29.69 Power Pole
SW 107.41 30" Oak
SE 82.72 6" Catalpa
NW 49.24 10" Twin Oak
NW 60.67 20" Oak

Liber 5, Pg. 52, 05-17-83
Set Cast Iron Monument
ENE 29.64 Power Pole
NW 81.76 Triple 16" Maple
West 47.84 12" Poplar
SW 116.66 4" Oak

Liber 6, Pg. 237, 09-15-92
Found Cast Iron Monument
ENE 23.95 $\frac{1}{2}$ " Top of Hydrant
SW 73.45 $\frac{1}{2}$ " Iron w/Cap
West 33.00 $\frac{1}{2}$ " Iron w/Cap
NW 92.20 $\frac{1}{2}$ " Top of 6" Steel Post filled w/conc
ENE 29.64 P.P.
West 47.84 12" Poplar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found broken off Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 1, Pg. 81, 09-24-71
SE 82.72 6" Catalpa
East 29.69 Power Pole

Liber 5, Pg. 52, 05-17-83
ENE 29.64 Power Pole
West 47.84 12" Poplar

Liber 4, Pg. 7, 11-30-79
East 29.69 Power Pole
SE 83.26 6" Catalpa
WNW 42.51 9" Poplar
NNW 74.46 6" Metal Guard Post (face)
WNW 47.84 13" Poplar


Liber 6, Pg. 237, 09-15-92
ENE 23.95 $\frac{1}{2}$ " Top of Hydrant
West 33.00 $\frac{1}{2}$ " Iron w/Cap
NW 92.20 $\frac{1}{2}$ " Top of 6" Steel Post filled with conc.
ENE 29.64 PP
West 47.84 12" Poplar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Broken off Cast Iron Monument in Monument Box

$\frac{1}{2}$ " Top Operating Nut on Hydrant
O.C. Remon. Tag & Nail in NW side 12" Catalpa
O.C. Remon. Tag & Nail in N side 13" Oak
O.C. Remon. Tag & Nail in side Twin 18" Oak

Az. 78° 23.93
Az. 140° 83.07
Az. 270° 41.30
Az. 328° 81.64



PA. 345 OTTAWA COUNTY
PEER APPROVED 12/13/94

Signed by Thomas E. Joiner Date 12-12-94
Surveyor's Michigan License No. 18435

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983