

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:46

For corners **COMMISSION**

Edythe Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	<u>M-3, SE Cor.</u>
	T _____ R _____	<u>Section 1</u>
	T _____ R _____	<u>Spring Lake Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, THOMAS E. JOINER in a field survey on 11-29- 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837	Liber 2, Pg. 53, 02-16-73
Post Set by John Mullet, D.S.	Found 3/8" Rod
N 55°W 25 14" Pine	WNW 20.86 22" Oak
S 06°W 70 10" Pine	WSW 22.13 18" Maple
	SE 54.31 25" Oak
	NE 50.80 14" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron Bar in monument box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 2, Pg. 53, 02-16-73
NE 50.80 14" Maple

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Maday D. Redwood



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1" Iron Bar with Cast Iron Monument in Monument Box replaced by Materials Testing.

O.C. Remon. Tag & Nail in NW side 18" Maple	Az. 48° 51.23
⊕ Top operating nut on Hydrant	Az. 148° 49.33
O.C. Remon. Tag & Nail in E side 46" Maple	Az. 210° 65.77
NE Cor. Hse #18393	Az. 252° 70.00
O.C. Remon. Tag & Nail in S side 14" White Pine	Az. 293° 49.75

Signed by Thomas E. Joiner
Surveyor's Michigan License No. 18435

Date 12-12-94