

**SURVEY &
REMONUMENTATION**

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>16W</u>	<u>M-11, SE Corner</u>
	T _____ R _____	<u>Section 25</u>
	T _____ R _____	<u>Spring Lake Twp</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 29 PM 1:39

Polycris Ballman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, THOMAS E. JOINER, in a field survey on 11-7-, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


05-1837	Liber 1, Page 295 03-8-72
Post Set By Calvin Britain, D.S.	Found Stone & Iron From Old County Surveyors Tie
S 21°E 11 lks 7" Beech	Set Cast Iron Monument
S 67°W 82 lks 8" Oak	E 16.91 Telephone Pole
	S 75°E 35.88 12" Apple
	SW 72.32 Power Pole
	SW 150.92 NE Cor. of Attached Garage

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.
Liber 1, Page 295
SW 150.72 NE Corn. of Attached Garage
SW 72.32 Power Pole
S 75° E 35.88 12" Apple

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Madison D. Peterson
207



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in NE side of Twin 12" Maple	AZ 131°	60.11
O.C. Remon Tag & Nail in S side of 9" Cherry	AZ 246°	59.78
O.C. Remon Tag & Nail in N side of Light Pole	AZ 80°	17.51
Q ₁ Top Operating Bolt on Hydrant	AZ 302°	48.18

Signed by Thomas E. Joiner Date 11-16-95
Surveyor's Michigan License No. 18435