

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ottawa Located In: Spring Lake Corner Code # Def #2
(County) Twp

1. Public Land Survey T 8N R 16W K-10
T R Reference
T R corner to
T R E 1/2 corner

2. Property Controlling S T R Section 26 and
in Section S T R Meander corner

3. Miscellaneous S T R on South Bank
Property in Sec. S T R of Grand River

RECORDED

96 DEC 20 PM 12: 20

Elizabeth S. Hollman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, in a field survey on 11/12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26	*	25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1/4 corner common to Sections 25 & 26
G.L.O. 1832 Britain
40.00 Set 1/2 mile post in Marsh
45.84 Grand River and set Meander Post
Raised a Mound No bearing trees
Marsh as before

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96

C.P. Englert

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 1/4 corner common to Sections 25 & 26
Corner and Meander Post Lost
Established corner by measuring North with 1832 Chain to Intersect line from K-9 to Found Iron Spike 1319.70' South of K-9. This is also East line of Oak Park Plat and West line of Plumwood Sub.

See Other Side

Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 1/4 corner common to Sections 25 & 26
Reference corner on line from K-9 to position of Meander Post (1832),
Set 3/4"x3' Iron Bar with O.C. Remon Cap
O.C. Remon nail & tag in NE Side 12" Maple S25°E 34.71'
O.C. Remon nail & tag in SE Side 30" Oak N54°E 55.72'
O.C. Remon nail & tag in NE Side 20" Pine N33°W 52.24'
O.C. Remon nail & tag in NE side 14" Aspen N65°W 33.25'
Waters edge of Grand River 60'± South

Signed by Carl P. Englert
Surveyor's Michigan License No. 18927

Date 12/13/1996

