

RE

FEB 24 2000

RECORDED

OTTAWA COUNTY REMONUMENTATION 99 JUL 30 PM 12:26

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Randy Scholtz
REGISTER OF DEEDS
OTTAWA COUNTY, MI

SECTION

For corners in
Ottawa

	Located In:		Corner Code #
	Chester Twp.	A-7 NW Cor.	
(County)	9W	13W	Sec. 19
1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S	T	_____
	S	T	_____
3. Miscellaneous Property in Sec.	S	T	_____
	S	T	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Randal D. Feenstra

March 22 99

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. by Rasselas Whitcomb
Sept. 17, 1838
Set Post
16" Beech N60°E 4 links
7" Sugar Maple S58°W 6 links

L-5, P-8, 1982 (Joiner)
Part B: Found Iron in monument box
40" Maple NNW 83.40
Power Pole NE 86.00

Part C: Set Cast Iron Monument
Power Pole NE 86.61
Maple NW 85.70
St. Sign SW 46.35
St. Sign SE 44.20

(Continued on Other Side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found: Broken Cast Iron Monument in monument box.
Nail in Power Pole AZ 45°55' 86.50'
Nail in 44" Maple AZ 332°15' 85.68'
St. Sign AZ 218°40' 46.27'

Accepted as a careful and faithful perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Broken Cast Iron Monument in monument box (See Sketch)	AZ 45°55'	86.50
Set Ottawa County Remon Nail & Tag in NW side of Power Pole	AZ 155°40'	149.35'
Ottawa County Remon Nail & Tag in SW side of Power Pole	AZ 332°15'	85.68'
Ottawa County Remon Nail & Tag in E side of 44" Maple	AZ 347°40'	212.84'
Ottawa County Remon Nail & Tag in E side of Power Pole	AZ 218°40'	46.27'
St. Sign		
Centerline E-W bituminous road (Gooding St.) North 1.1'		
ON Centerline N-S gravel road (Squires Rd.)		

\$11.00 CORNER
Receipt #52389

PA. 345 OTTAWA COUNTY
PEER APPROVED 7/12/99

Signed by *Randal D. Feenstra*
Surveyor's Michigan License No. 32725

Date May 14, 1999

Muskegon County Information

M-7 L-1118, P. 937 1977 (Englert)

3/4" Rod in Monument Box

Fence Post NW 45.79'

Power Pole NE 86.52'

St. Sign SE 43.35'

St. Sign SW 52.5'

SURVEY &
RECORDS

FEB 24 2000

SECTION

