

FEB 24 2000

RECORDED

99 JUL 30 PM 12:26

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in  
Ottawa

*Dan Scholten*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Located In:	Chester Twp.	Corner Code #
	9N 13W	A-12 W 1/4 Cor.
1. Public Land Survey	T___ R___	Sec. 31
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Randal D. Feenstra March 10 99

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. Not Set L-6 P-113 1990 (Joiner)  
 A-12 Found Cast Iron Monument  
 SW Garage Cor. ENE 106.17  
 NW House Cor. NE 152.40  
 12" Cherry NW 82.96  
 4" Elm SW 50.70

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 Found: Broken Cast Iron Monument in Gravel  
 Found NW House Cor. AZ 41°45' 152.34'  
 Found SW Garage Cor. AZ 81°30' 106.11'

PA. 845 OTTAWA COUNTY  
 PEER APPROVED 7/12/99  
*YD*

This position not established by original government surveyors. This location is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 Broken Cast Iron Monument in gravel (See Sketch)  
 NW Cor. House Foundation AZ 41°45' 152.34'  
 SW Cor. Garage Foundation AZ 81°30' 106.11'  
 Rebar in gravel shoulder of road AZ 315°30' 27.48'  
 NW Cor., Sec. 31 North 2638.94  
 Centerline N-S gravel Rd. (48th Ave.) West 3.5'



Signed by *Randal D. Feenstra*  
 Surveyor's Michigan License No. 37275

Date May 14, 1999

1881  
SURVEY &  
RE

FEB 24 2000

SECTION

