

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Ottawa

(County)	Located In:	Corner Code #
1. Public Land Survey	Chester Twp. 9N R 13W	C-2, E 1/4 cor. Sec. 6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

95 NOV 29 PM 1:37

Ralph L. Kullman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

Randal D. Feenstra November 6 95

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	•	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1838)	L-3, P-337, (1979)		
Rasselus Whitcomb	1" Pipe		
10" Beech S14°E 10 lks.	P. Pole	W	46.00'
8" Maple N31°W 9 lks	30" Maple	NE	29.71'
	30" Maple	NNE	52.48'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M. in box Accepted as a careful and faithful perpetuation of the position of the original corner.

Pk in N side P. Pole W 46.00'


P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Madog P. Medinell
MDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2	C.I.M. in box		
	Ottawa County Remon Nail & Tag in N side P. Pole	272°	45.98'
	Ottawa County Remon Nail & Tag in E side P. Pole	347°	206.32'
	Ottawa County Remon Nail & Tag in NW side 8" Ash	81°	51.12'
	Ottawa County Remon. Nail & Tag in W side 12" Cherry	165°	135.22'

0.5' W of centerline 40th Ave.



Signed by *Randal D. Feenstra*
37275

November 6, 1995

Date _____

Surveyor's Michigan License No. _____