

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

93 NOV -8 PM 1:59

Phyllis Kallman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|------------------|
| 1. Public Land Survey | T | 9N | R | 13W | C-5, NW COR. |
| | T | | R | | Sec. 17, Chester |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Randal D. Feenstra in a field survey on October 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|-------------------------------|--------------------------------|--|
| C-5: | | |
| L.C.R.C.# L-2, P-820 (5-1-75) | L.C.R.C.# L-4, P-257 (12-3-81) | |
| Cast Iron Monument | Cast Iron Monument | |
| 36" Maple NW 59.97' | 26" Maple SW 53.53' | |
| P. Pole WNW 79.40' | P. Pole SW 77.70' | |
| 28" Ash SW 53.95' | 28" Maple NW 59.79' | |
| | SE Cor. Conc. Porch NW 110.26' | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-5: Found Cast Iron Monument in Box - accepted as a careful and faithful perpetuation of the position of the original corner.
- | | | |
|---------------------------|-------|---------|
| Nail in SE side 28" Ash | S50°W | 53.53' |
| Nail in S. side 30" Maple | N50°W | 59.79' |
| PK in N. side P.P. | S60°W | 77.68' |
| SE cor. conc. porch | N40°W | 110.15' |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-5: Cast Iron Monument in Box
- | | | |
|---|-------|---------|
| O.C. Remon. Nail & Tag in S. side 30" Maple | N50°W | 59.78' |
| O.C. Remon. Nail & Tag in N. side P.P. | N65°W | 79.42' |
| O.C. Remon. Nail & Tag in SE side 28" Ash | S50°W | 53.53' |
| SE cor conc. porch to Hse.#22419 40th Ave. | N40°W | 110.15' |
- 1' W. & 1' N. of CL "X" 40th Ave. & Hoover Street.



Signed by Randal D. Feenstra

Date 10-18-93

Surveyor's Michigan License No. 37275