

**SURVEY & REMONUMENTATION**

OCT 24 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 OCT -7 PM 12:34

*D. J. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa (County) Located In: Corner Code #

1. Public Land Survey	T <u>9N</u> R <u>13W</u>	<u>C-9, SW COR.</u>
	T _____ R _____	<u>Sec. 20, Chester</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Randal D. Feenstra, in a field survey on April 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1838) Liber 5, Page 251 (1986)

8" W. Oak N80°E 17.8'	CAST IRON MONUMENT
4" Maple S75°W 20.5'	Wood post SE 20.76
POST	3" Tree NE 34.76
Rasselas Whitcomb	Twin 14" Poplar WNW 60.69
	30" Oak WSW 74.40

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: Cast iron monument in monument box - accepted as a careful and faithful perpetuation of the position of the original corner.

Found witnesses:

Nail in NE side 32" Oak WSW 73.34'

**P.A. 345 OTTAWA COUNTY**  
PEER APPROVED 9/22/94  
*Gordon P. Fedoruk*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Cast Iron Monument in Monument box

O.C. Remon. Nail & Tag in NW side P.P.	N50°E 65.00'
O.C. Remon. Nail & Tag in N side P.P.	N90°W 57.42'
O.C. Remon. Nail & Tag in SE side 32" oak	S60°W 74.28'
O.C. Remon. Nail & Tag in SE side triple 10" oak	S85°W 76.97'

On CL "x" 40th Avenue & Coolidge Street



Signed by Randal D. Feenstra Date April 28, 1994

Surveyor's Michigan License No. 37275