

SURVEY & REMONUMENTATION

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:46

For corners in **COMMISSION**

Phyllis Anderson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>13W</u>	D-3, N 1/4 Cor.
	T _____ R _____	Sec. 8
	T _____ R _____	Chester Twp.
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal D. Feenstra, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|--|---|--|
| G.L.O. by Rasselas Whitcomb
Sept. 17, 1838
POST
14" Lymm S87 30'E 15 links
9" Beech S79 W 15 links | L-2, P-11 (1972)
IRON PIPE
T. Pole NW 63.09'
18" Maple NNE 64.56'
18" Maple NE 59.22'
P. Pole NE 67.20'
P. Pole SSE 39.57'
St. Sign SSW 28.38' | L-5, P-49 (1983)
C.I.M.
P. Pole SSE 39.90'
T. Pole NW 64.22'
21" Maple NE 65.10'
P. Pole ENE 67.43' |
|--|---|--|


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found: C.I.M. in Box (No Cover) and is accepted as a careful and faithful perpetuation of the position of the original corner.

Nail & Tag in SW side P. Pole NE 67.10'
Pk Nail in E side P. Pole SSE 40.37'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Walter D. Newbold

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-3 C.I.M. in Box
- O.C. Remon. Nail & Tag in S side P. Pole N65 E 67.31'
- O.C. Remon. Nail & Tag in E side P. Pole S10 E 40.34'
- O.C. Remon. Nail & Tag in S side 24" Maple N30 E 89.16'
- O.C. Remon. Nail & Tag in S side Fence Post N30 W 95.33'
- 1' E of CL "X" 36th Avenue and Truman Street



Randal D. Feenstra
Randal D. Feenstra

Signed by _____ Date December 8, 1994
Surveyor's Michigan License No. 37275