

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa
(County)

Located In: Corner Code #

1. Public Land Survey	Chester Twp.		E-10, E 1/4 cor. Sec. 29
	T <u>9N</u> R <u>13W</u>		
	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		

RECORDED

95 NOV 29 PM 1:36

Ralphie Ballman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal D. Feenstra, in a field survey on Nov 6, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1838)	L-5, P-5, (1982)		
Rasselas Whitcomb	C.I.M.		
14" Sugar N22°W 19 lks.	18" Ash	W	74.34'
8" Sugar S43°E 20 lks	Cut-off T. P.	ENE	31.38'
	5" Ash Clump	E	46.60'
	10" Pine	SE	74.39'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Kelley P. Redwood
SPN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: Broken C.I.M.: Accepted as a careful and faithful perpetuation of the position of the original corner.
Pk in S side cut-off P. Pole ENE 31.40'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10	_____ C.I.M.		
	Set Ottawa County Remon Nail & Tag S side cut-off P. Pole	N69°E	31.36'
	Set Ottawa County Remon Nail & Tag N side Ash	N85°W	74.36'
	NE Cor. Block Fndn. of Porch of abandoned house	N26°W	110.79'
	Set Ottawa County Remon Nail & Tag W side 32" Elm	S 4°E	475.25'

Centerline 32nd Avenue(Bit Road)

Signed by Randal D. Feenstra
Surveyor's Michigan License No. 37275

Date November 6, 1995