

SURVEY & REMONUMENTATION

OCT 24 1994

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE

94 OCT -7 PM 12:34

Filing Requirement of Act 74, Mich. P.A. 1970

*Dorothy Redman*  
REGISTER OF DEEDS  
OF TAWA COUNTY, MI

COMMISSION

For corners in

Ottawa

(County)

Located In:

Corner Code #

- |                                    |   |           |   |            |                  |
|------------------------------------|---|-----------|---|------------|------------------|
| 1. Public Land Survey              | T | <u>9N</u> | R | <u>13W</u> | E-13, SE COR     |
|                                    | T | ___       | R | ___        | Sec. 32, Chester |
|                                    | T | ___       | R | ___        | ___              |
|                                    | T | ___       | R | ___        | ___              |
| 2. Property Controlling in Section | S | ___       | T | ___        | ___              |
|                                    | S | ___       | T | ___        | ___              |
| 3. Miscellaneous Property in Sec.  | S | ___       | T | ___        | ___              |
|                                    | S | ___       | T | ___        | ___              |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randal D. Feenstra in a field survey on May 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

O.C. (1838)	Liber 1, Page 621 (1972)	Liber 6, Page 118 (1990)
~ Beech N38°E 32.3'	1/2 Iron Pipe	C.I.M.
~ Beech N36°W 23.8'	PP NE 58.83	TP NE 59.12
ST	24" Maple SW 32.98	8-13 Twp. cor E 88.55
sselas Whitcomb	22" Maple SE 36.62	18" Maple SE 109.82
		22" Maple SW 30.71

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: Cast Iron Mon. in Mon. Box - accepted as a careful and faithful perpetuation of the position of the original corner.

Found Witnesses:

Nail in NW side PP	NE 59.11'
Nail in NW side 30" Maple	SW 30.73'
Mon. in Box, Sec. 4 & 5, T8N, R13W	E 88.45'


PA. 345 OTTAWA COUNTY

PEER APPROVED 8/22/94

*Gordon P. Redwell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Cast Iron Mon. in Mon. Box		
O.C. Remon. Nail & tag in E side PP	N30°W	113.92'
O.C. Remon. Nail & tag in SE side PP	N45°E	59.16'
O.C. Remon. Nail & tag in E side 30" Maple	S30°W	30.10'
O.C. Remon. Nail & tag in E side 26" Maple	S60°W	54.70'
Wright Township Corner		
0.5' N of CL "X" Wilson Street and 32nd Avenue.		



Signed by Randal D. Feenstra

Date May 9, 1994

Surveyor's Michigan License No. 37275