

**OTTAWA COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ottawa

Located In:	Chester Twp.	Corner Code #
	9N 13W	F-3, N 1/4 cor.
1. Public Land Survey	T___ R___	Sec. 9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

RECORDED  
96 DEC 17 AM 10:42  
*Randy D. Feenstra*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randal D. Feenstra, in a field survey on Oct. 7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1838)		L-3, P-265, (1978)		L-5, P-272 (1987)
Rasselas Whitcomb		Iron		Pk Nail
Post		16" Twin Maple	S10°E 57.20'	12" (dead) Elm N 39.0'
16" Sugar Maple	N6°W 11 lks.	6" Elm	N39.60'	24" Maple ENE 233.90'
10" Sugar Maple	S1°E 13 lks.	29" Maple	N82°E 133.90'	P. Pole S 74.35'
				Metal Bldg. SW 105.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3 Found: PK Nail

Nail W.side P. Pole	S	74.38'
NE Cor. Metal Bldg.	SW	105.10'
24" Maple	ENE	233.5'


P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11-11-96  
*Randy D. Feenstra*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3 Set Ottawa County Remon Bar & Cap in New Monument Box

"X" in W end 12" conc. pipe	N	5°E	25.38'
"X" in E end 12" conc. pipe	S	60°E	41.77'
Ottawa County Remon Nail & Tag in E side Fence Post	S	10°E	37.96'
Ottawa County Remon Nail & Tag in N side 6" Juniper	S	45°W	86.92'
Ottawa County Remon Nail & Tag in S side 24" Maple	N	81°E	234.12'

1'S of Centerline Truman, 8'W of Fence Line to South, 3' E of Centerline Swale to North



Signed by *Randal D. Feenstra*  
Surveyor's Michigan License No. 37275

Date October 7, 1996