

SURVEY & MONUMENTATION

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa

Located in:	Corner Code #
Chester Twp. 9N 13W	G-10, E 1/4 cor. Sec. 28
T___ R___	_____
T___ R___	_____
T___ R___	_____
T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____

RECORDED

95 NOV 29 PM 1:36

Rachel Redman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Randal D. Feenstra, in a field survey on Nov 6, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1838)	L-3, P-110, (1976)	L-5, P-258 (1986)
Rasselas Witcomb	Steel Bar	C.I.M.
30" Beech S7°E 29 lks.	18" Basswood E 35.20'	Fence Post W 32.85'
20" Beech N30°E 25 lks	Guy Pole NNW 177.95'	7" Tree SW 120.37'
		21" Tree E 35.35'
		5" Tree ESE 39.05'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M. in mon.box Accepted as a careful and faithful perpetuation of the position of the original corner.

Nail & Tag N side Fence Post W 32.88'
Nail & Tag S side 26" Maple E 35.30'

RA. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Randal D. Feenstra

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10	C.I.M. in box	W 36.91'
	Set Ottawa County Remon Nail & Tag S side fence Post	S19°W 120.34'
	Set Ottawa County Remon Nail & Tag E side 16" Elm	S53°E 96.95'
	Set Ottawa County Remon Nail & Tag N side 24" Oak	N8° W 180.46'
	Set Ottawa County Remon Nail & Tag E. side P. Pole	
	0.5' E of centerline 24th Ave.	



Signed by *Randal D. Feenstra*
Surveyor's Michigan License No. 37275

Date November 6, 1995