

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa

Located in: Corner Code #

(County)	Located in:	Corner Code #
1. Public Land Survey	Chester Twp. 9N 13W H-13, S 1/4 cor.	
	T___ R___	Sec. 34
	T___ R___	
	T___ R___	
	T___ R___	
2. Property Controlling in Section	S___ T___ R___	
	S___ T___ R___	
3. Miscellaneous Property in Sec.	S___ T___ R___	
	S___ T___ R___	

RECORDED

95 NOV 29 PM 1:36

Ralph A. Holman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal D. Feenstra, in a field survey on Nov 6, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1837)	L-6, P-105, (1991)
Noah Brookfield	C.I.M.
10" Sugar NW 26 lks.	Wright Cor. E 60.00'
10" Walnut NE 24 lks	16" Apple SE 76.95'
	P. Pole SW 109.82'
	12" Apple NW 87.69'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Randal D. Feenstra
RD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C. I. M. in Mon. Box. Accepted as a careful and faithful perpetuation of the position of the original corner.

Nail in NW side P. Pole SW 109.73'
Nail in N side 16" Apple SE 76.91'
Wright Twp. Corner E 60.02'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13	C.I.M. in Box	
	Set Ottawa County Remon Nail & Tag NE side P. Pole	N74°W 119.13'
	Set Ottawa County Remon Nail & Tag W side 14" Pine	S68°W 113.41'
	Set Ottawa County Remon. Nail & Tag NE side P.Pole	S35°E 72.89'
	NE Cor. Brick Barn	S17°W 148.01'
	Wright Cor.	E 60.02'
	Centerline Wilson St. (Bit Road) 1.3' N	



Signed by *Randal D. Feenstra*
Surveyor's Michigan License No. 37275

Date November 6, 1995