

SURVEY & REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa
 (County)

Located In: Chester Twp. Corner Code #

1. Public Land Survey	T	R	I-2, E 1/4 cor.
	T	R	Sec. 3
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

RECORDED

95 NOV 29 PM 1:35

R. J. ...
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randal D. Feenstra, in a field survey on Nov 6, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1838)	L-4, P-267, (1981)
Rasselas Witcomb	C.I.M.
14" Beech S66°E 22 lks.	34" Oak E 30.64'
8" Sugar N78°W 21 lks	30" Hemlock SE 68.13'
	20" Cedar SE 36.46'
	P. Pole W 28.62'

PA. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M.

Accepted as a careful and faithful perpetuation of the position of the original corner.

Nail N side 36" Oak E 30.37'

Note: Removed C.I.M. as part of Ottawa County Road Comm. Project. Set new Bar & Cap.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2	Set Ottawa County Remon. Bar & Cap in Mon. Box	
	Set Ottawa County Remon Nail & Tag N. side P. Pole	
	Set Ottawa County Remon Nail & Tag S. side 36" Oak	W 51.01'
	Set Ottawa County Remon Nail & Tag N. end 12" CMP	S76°E 30.58'
	Set Ottawa County Remon Nail & Tag NE side wood gate post	N33°E 45.68'
		N53°W 41.58'

Centerline 16th Avenue (Bit Road)

Signed by Randal D. Feenstra
 Surveyor's Michigan License No. 37275

Date November 6, 1995