

SURVEY & REMONUMENTATION

JUN 28 1999

SECTION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

98 NOV -4 PM 2:32

Randy [Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located in:	Corner Code #
	Chester Twp.	
1. Public Land Survey	T 9N R 13W	I-4
	T ___ R ___	E 1/4 Cor., Sec. 10
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal D. Feenstra, in a field survey on August 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1838)	Liber 6, P. 112 (1991)
Rasselus Whitcomb	1/2" Rod in Monument Box.
10" Beech N51 1/2°E 32 lks.	6" Cherry E 59.03'
10" Beech S12°W 22 lks.	6" Cherry ESE 85.58'
	4" Cherry SE 76.13'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: 1' diameter hole in bit. - nothing in it
Found no previous witnesses

Set corner 1/2 way and on line between I-3 and I-5
Falls in West side of existing hole

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set	Ottawa County Remon Bar and Cap in new Monument Box		
Set	Ottawa County Remon Nail & Tag in W side 6"x6" Mail Box Post	AZ 169°45'	98.71'
Set	Ottawa County Remon Nail & Tag in NE side P. Pole	AZ 346°15'	258.15'
Set	Set Chiseled "X" N end 12" Conc. Culv.	AZ 200°30'	82.51'
Set	Set 1/2" iron Rod	AZ 71°40'	42.73'
	On CL N-S Bit. Rd. (16th Ave.)		

10/19/98
[Signature]



Signed by *Randal D. Feenstra*
Surveyor's Michigan License No. 37275

Date October 16, 1998

SURVEY &
REMONUMENTATION

JUN 28 1999

SECTION

