

SURVEY & REMONUMENTATION

NOV 10 1993

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OTTAWA COUNTY REMONUMENTATION

For corners in
OTTAWA

(County)

Located In:

Corner Code ##

CHESTER TWP.

1. Public Land Survey

T 9N	R 13W	J-9	S	Cor-23	
T 9N	R 13W	K-9	SE	Cor-23	
T	R				
T	R				
S	T	R			
S	T	R			
S	T	R			
S	T	R			

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED

1993 SEP 29 PM 3:14

Regina Johnson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Randal D. Feenstra, in a field survey on July 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


J-9 = LCRC#'s L-2, P-183; L-5, P-163

K-9 = LCRC#'s L-4, P-223

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9
Found Cast Iron Monument in Box
Per LCRC # L-5, P-163

K-9
Found Cast Iron Monument in Box
And Witnesses Per
LCRC # L-4, P-223



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

~ J-9 - Cast Iron Monument per L-5, P-163, Ottawa County, MI, and is accepted as a careful and faithful perpetuation of the position of the original corner.

"X" in West end 15" concrete culvert	N15°E 24.84	faithful perpetuation of the position of the original corner.
"X" in East end 15" concrete culvert	N55°E 39.36	
O.C. Remon. Nail & Tag in 8" Elm	S5°W 35.36	
O.C. Remon. Nail & Tag in twin 24" Sycamore	S15°E 133.34	

© CL Coolidge, ON Tree line to N. & S.

- K-9 - Cast Iron Monument per L-4, P-223, Ottawa County, MI, and is accepted as a careful and faithful perpetuation of the position of the original corner.

O.C. Remon. Nail & Tag in 6" Apple	S20°E 71.57	faithful perpetuation of the position of the original corner.
O.C. Remon. Nail & Tag in 6" Maple	N70°W 99.54	
O.C. Remon. Nail & Tag in 8" Maple	N25°W 100.25	
"X" in West end 12" concrete culvert	S35°W 25.95	

© CL 8th & Coolidge
Signed by Randal D. Feenstra Date July 20, 1993
Surveyor's Michigan License No. 37275

