

SURVEY & REMONUMENTATION

OCT 24 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 OCT -7 PM 12:34

Elizabeth A. Sullivan
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 13W	J-13, S 1/4 COR SEC. 35, CHESTER
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Randal D. Feenstra in a field survey on May 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.C. (1838) Liber 5, Pg. 318 (1988)

10" Beech	N55°W	16.5	C.I.M.	
12" Sugar	N49°E	13.2	PP	N 35.68
POST			10" Apple	SW 71.73
Rasselas Whitcomb			10" Apple	S 46.52
			10" Apple	SE 62.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M. in Box - accepted as a careful and faithful perpetuation of the position of the original owner.

Found Witnesses:

Nail in W side 10" Apple SE 62.05
Nail in W side 10" Apple S 46.48

PA. 345 OTTAWA COUNTY

PEER APPROVED 8/22/94

Randal D. Feenstra

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Cast Iron Mon. in Box		
O.C. Remon. Nail & tag in E side PP	N00°E	35.74
O.C. Remon. Nail & tag in S side 12" Basswood	N65°W	112.75
O.C. Remon. Nail & tag in N side 10" Apple	S50°W	71.56
O.C. Remon. Nail & tag in W side 10" Apple	S20°E	49.09
2' S of CL Wilson Street		



Signed by Randal D. Feenstra

Date May 20, 1994

Surveyor's Michigan License No. 37275