

RECORDED

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 JUL 24 PM 2: 24

For corners in
Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	9N	R	13W	K-4, E 1/4 Cor.
	T		R		Sec. 11
	T		R		Chester Twp.
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Russell Whitcomb
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Randal D. Feenstra

September 21

95

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. by Russelas Whitcomb Sept. 17, 1838 POST 11" Sugar 10" Sugar	S 15°E 17 links N 71°W 25 links	L-2, P-519, 1974 "T" Iron CL N.5 Gravel, Fence E-W 12" 10" W. Cherry 10" Poplar 12" Oak	N85°W 54.72' N 18°E 62.53' E 77.15'	L-3, P-253, 1977 "T" Iron Lum. Poplar 14" Oak 20" Maple 12" Cherry	N19°E 62.50' S88°E 77.10' S09°E 173.20' N87°W 55.36'
L-4, P-233, 1981 C.I.M. 5" Elm 12" Poplar	E 34.87' NNE 62.52'	24" Maple	S09°E 173.20'		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found C.I.M.
Nail and tag in W side 20" Poplar NNE 62.54'
Nail and tag in S side 18" Oak E 77.02'

Accepted as a faithful perpetuation of the position of the original corner.

P.A. 348 OTTAWA COUNTY
PEER APPROVED 10-21-96


[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 C.I.M. in Gravel Road

Ottawa County Remon. Nail and Tag in W side 20" Poplar
Ottawa County Remon. Nail and Tag in S side 18" Oak
Ottawa County Remon. Nail and Tag in E side 10" Poplar
Ottawa County Remon. Nail and Tag in W side 30" Maple
On centerline with tree line to East

N15°E 62.09'
N90°E 76.96'
S10°W 121.93'
S10°E 173.39'



\$ 9.00 CORNER

Signed by Randal D. Feenstra
Randal D. Feenstra

Date September 21, 1995

Surveyor's Michigan License No. 37275

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19
REVISED MAY 14, 19
REVISED JAN., 19