

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:48

Deborah L. Callman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>13W</u>	L-3, N 1/4 Cor.
	T _____ R _____	Sec. 12
	T _____ R _____	Chester Twp.
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal D. Feenstra, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. by Rasselas Whitcomb Sept. 17, 1838 POST 26" Sugar S31 E 28 links 11" Beech N 25 W 18 links	L-5, P-12, 1982 SE cor. Brk Hse N45 W 230.0' C.P. S50 W 95.4 C.P. S80 E 261.60'	L-5, P-163, 1984 C.I.M. P. Pole ENE 207.22 Fence Post N 36.13 2" Tree NW 66.1 P. Pole SW 95.59
--	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found: C.I.M. in box (No Cover) and is accepted as a careful and faithful perpetuation of the position of the original corner.

Nail in NW side P.Pole SW 95.62'
Nail in side Fence Post N 36.13'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Rodney P. Nedewell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 C.I.M. in box
O.C. Remon Nail & Tag in NW side P.Pole S45 W 95.62'
O.C. Remon. Nail & Tag in W side Fence Post N00 E 36.21'
O.C. Remon Nail & Tag in W side 5" Spruce N30 W 56.71'
"X" in W side 12" conc. culv. N70 E 98.55'
On CL "X" Truman Street



Randal D. Feenstra

Signed by Randal D. Feenstra Date December 8, 1994

Surveyor's Michigan License No. 37275

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983