

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa

Located In: Corner Code #

(County)		Chester Twp.	
		9N 13W	M-6, E 1/4 cor.
1. Public Land Survey	T	R	Sec. 13
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

RECORDED

95 NOV 29 PM 1:34

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal D. Feenstra, in a field survey on Nov 6, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1837)	L-4, P- 66, (1980)	L-6, P-110 (1991)	
Noah Brookfield	Re-rod	C.I.M.	
10" Beech	N24°W 24 lks.	P. Pole N85°E 54.58'	5" Cherry W 150.07'
9" Beech	S13°W 60 lks	on centerline gravel road	P. Pole E 54.67'
			1" Pipe NW 43.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M. in box Accepted as a careful and faithful perpetuation of the position of the original corner.

Pk. in S side of P. Pole E 54.62'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

Kendry D. Pedersen
YDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6	C.I.M. in box	
	Ottawa County Remon Nail & Tag in SE side P. Pole	11° 295.70'
	Ottawa County Remon Nail & Tag in S side P. Pole	90° 54.64'
	Ottawa County Remon. Nail and Tag in NE side P. Pole	169° 296.94'

on centerline Kenowa

Signed by *Randal D. Feenstra*
Surveyor's Michigan License No. 37275

Date November 6, 1995

