

**SURVEY & REMONUMENTATION**

OCT 24 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 OCT -7 PM 12:34

*Elizabeth Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
Ottawa  
(County)

Located In: Corner Code #

1. Public Land Survey	T 9N R 13W	M-13, SE COR
	T _____ R _____	Sec. 36, Chester
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal D. Feenstra, in a field survey on July 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1838)	Liber 6, Page 103 (1991)
30" Elm N87°W 25.1	C.I.M. (Kent County)
30" Maple N38°E 26.4	PP NE 69.52
POST	Tel Ped SE 53.00
Rasselas Whitcomb	"X" in Culv. SW 73.24
	TP NW 123.67

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M. (Kent County) - accepted as a careful and faithful perpetuation of the position of the original corner.

Found Witnesses:

Pk in NW side PP	N45°E	69.48'
"X" in W end culvert	S35°W	73.15'
Tel Ped	S45°E	53.02'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 8/22/94

*Gordon D. Medwell*

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 C.I.M. (Kent County)  
I.C. Remon: Nail & tag in E side PP 123.65'  
I.C. Remon: Nail & tag in SE side PP 69.20'  
"X" in E end culv. S30°E 74.22'  
"X" in W end culv. S35°W 73.15'  
In CL "X" Kenowa Avenue and Wilson Street



Signed by Randal D. Feenstra

Date July 13, 1994

Surveyor's Michigan License No. 37275

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983