

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
(County)

Located in:

Corner Code #

1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T 46N R 39W	11
	S	T 46N R 39W	11
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sep 24 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(11-Sec.1) Southwest 1/16 corner, Section 1. Corner previously recorded in 1991 by Joseph W. Lett, RLS #21576, in Liber 3 Page 153, Ontonagon County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 1) Recovered the 1991 witness monuments as described in the previous record. A retracement of Section 1 and of the 1991 Lett survey revealed the 1991 survey to be erroneous in several respects. The previously recorded witness monuments are rejected as representing the position of this corner. I established the corner at the intersection of straight lines connecting opposite 1/16 corners. The position for the corner falls in the Middle Branch of the Ontonagon River and cannot be monumented. I established two WITNESS CORNERS to the 1/16 corner, the first being on the 1/16 line 71.76' Westerly of the corner, the second being on the 1/16 line and 169.10' Easterly. Both witness positions are marked with a 1" I.D. iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986". Both were set in rock mounds and cemented in place with portland cement concrete. Corners placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1" x 18" iron pipe with plastic cap 71.76' W'ly and on the 1/16 line. Blazed and scribed the following: 8" Y. Birch S22N 5.4' "MC BT" 9" Spruce N23N 8.6' "MC BT" 7" Cedar N11E 11.2' "MC BT" 11" Spruce S39E 21.8' "MC BT" Bearings are magnetic. Distances to notch in lower blaze.	(11) Set 1" x 12" iron pipe with plastic cap 169.10' E'ly and on the 1/16 line. Blazed and scribed the following: 5" Cedar S01E 14.2' "MC BT" 12" Cedar S41W 8.4' "MC BT" 10" R. Pine S86W 6.0' "MC BT" 7" W. Pine S78E 21.2' "MC BT" Bearings are magnetic. Distances to notch in lower blaze.
--	---



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2/18/98

For the Michigan Department of Natural Resources - Forest Management Division