

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon

(County)

Located in:

Corner Code #

1. Public Land Survey	T 46N R 39W	M2
	T 46N R 39W	L1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

L1 Sep 29 1997

M2 Sep 23 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(M2) Quarter corner common to Section 1 T46N-R39W and Section 6 T46N-R38W. Corner established in 1847 by John Burt: "Set Qr. Section post Aspen 10 S28W 18, do 12 N53E 19". Found no subsequent record.

(L1) Quarter corner common to Section 1 T46N-R39W and Section 36 T47N-R39W. Corner restored and remonumented in 1986 by R.L. Drahn RLS # 21564, and described in Liber 2, Page 420, Ontonagon County Record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M2) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. I regard the corner as lost and reestablish the corner 40 chains, proportionate to the original record, north of M3 and on a line of mean true bearing between M1 and M3. Distances north and south to these corners were measured by GPS observations and determined to be 2683.03' and 2632.99', respectively. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

(L1) Recovered the 1986 monument, in good condition, and at record bearing and distance from the 1986 accessories. The W. Spruce NW is now dead. Marked one new witness to replace this tree, as described below. Corner recovered and rewitnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M2) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:
9" Sugar S45W 135.1' "1/4S HBT"
5" Maple S84W 174.7' "1/4S HBT"
11" W. Birch N75W 192.6' do
15" Spruce N43W 230.4' "1/4S HBT"
Placed a squared cedar post adjacent.
Bearings are magnetic. Distances are to notch in lower blaze.

(L1) Found 2" dia. aluminum monument with 3 1/4" dia. aluminum cap #21564.
Blazed and scribed the following:
6" W. Spruce N79W 25.7' "1/4S HBT"
A 2-track road is 38' West of the corner. Bearings are magnetic.
Distance to notch in lower blaze.



Signed by

Stephan J. Szyszkoski

Date

2/18/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division