

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
In Section

S 1 T 46N R 39W 12

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

Sep 23 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (12-Sec. 1) South 1/16 corner of Section 1. Corner previously recorded in 1991 by Joseph W. Lett, RLS #21576 in Liber 3 page 152, Ontonagon County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec.1) Recovered the 1991 monument as described in the previous record. A retracement of Section 1 and of the 1991 Lett survey revealed that the 1991 survey was erroneous in several respects. I rejected the Lett monument as representing the position of the corner. I established the corner midway and on a straight line between the Center of Section 1 and the South 1/14 corner of Section 1. The South 1/4 corner falls in the Bond Falls Flowage. It's unmonumented position was determined by proportionate measurement, according to the original record between the SW and SE corners of Section 1. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a yellow plastic cap which is stamped "MICH DNR PS 33986", set flush with the ground. Corner placed and witnessed by D.Lampela and B.Wheeler. The 1991 monument was found 7.00' north of this position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1" pipe with plastic cap.

Blazed and scribed the following:

16" Maple N43W 30.2' 1/16S BT

6" Sugar N73E 30.2' 1/16S BT

5" Sugar S33E 30.4' 1/16S BT

6" Sugar S73W 9.4' 1/16S BT

Bearings are magnetic. Distances to notch in lower blaze. Set a squared post adjacent.



Signed by

Stephan J. Szyszkoski

Date 2/10/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division