

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ontonagon  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>39W</u>	<u>K3</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>1</u> T <u>46N</u> R <u>39W</u>	<u>15</u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 29 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	H
1													
2	6	5	4	3	2	1							
3											●	●	
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 (K3) Corner common to Sections 1-2-11-12. Corner reestablished in 1986 by R.L. Drahn, RLS #21564 from feature calls and measurements to adjacent corners. Recorded in Liber 2 Page 417, Ontonagon County Records.  
 (15-Sec. 1) West 1/16 corner between Sections 1 and 12. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) Recovered and accepted the 1986 USFS monument as described in the previous record. The Maple MBT S65N is dead. The remaining 1986 witnesses are as previously recorded. Marked two new accessories as described below. This corner is being recorded in order to update the accessories. Corner re-witnessed by D.Lampela and B.Wheeler, Baraga District Office.  
 (15-Sec.1) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Section corner 1333.19' West the South 1/4 corner of Section 1 1333.19' East. The South 1/4 corner falls in the Bond Falls Flowage. It's unmonumented position was determined by proportionate measurement, according to the original record between the SW and SE corners of Section 1. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Found 2" dia. aluminum monument with 3 1/4" dia. aluminum cap # 21564.	(15) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:	Blazed and scribed the following:
3" Maple S81W 57.6' "S11 MBT"	13" Hemlock S75E 6.1' "1/16S BT"
4" W. Birch N35E 68.6' "S1 MBT"	7" Twin Sugar N37E 27.0' "1/16S BT"
Bearings are magnetic. Distances are to notch in lower blaze.	12" Hemlock N18W 33.2' "1/16S BT"
	5" Maple S67W 42.2' "1/16S BT"
	Placed a squared maple post adjacent.
	Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/18/98

For the Michigan Department of Natural Resources - Forest Management Division