

**SURVEY &
REMONUMENTATION**

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

ONTONAGON
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>46N</u> R <u>39W</u> | <u>F-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4/12 1994
11:05
3
Judith Boehm
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

¼ Corner, Sections 4, 9; T46N., R39W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Richard L. Drahn, in a field survey on August 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Zelotes B. Searls, U.S. Deputy Surveyor, on July 13, 1851.
Original bearing trees:

W. Pine	24"	S.20°W.	12 links	(7.92 feet)
Sugar	14"	N.55°E.	45 links	(29.70 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing trees found. Re-established corner by single proportion measure on line between the N.E. and the N.W. corners of Section 9.

PEER GROUP

Approved

Earl W. Appenkamp 04-07-94
Ontonagon Co. Rep.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position and 6" below surface of a E-W county road I set a 2" diameter by 12" long concrete filled, galvanized iron pipe with a 3" brass cap stamped to read: T.46N., R.39W.; ¼; S.4, S.9; 1993; R.L.S. 21564: from which I established the following new blazed and scribed bearing trees and reference objects:

Wisconsin-Michigan Power Co. Pole #75-2106	S.78°E.	134.92 feet
8" Balsam	S.15°W.	47.25 feet
8" Red Maple	S.32°E.	63.91 feet

A 6' steel sign post N.01°W. 24.31 feet
A standard 30" long, aluminum R.M. with a 3¼" aluminum cap, stamped to indicate true corner position bears North, 23.00 feet.

Signed by Richard L. Drahn Date February 10, 1994

Surveyor's Michigan License No. 21564
U.S.F.S. E-11