

# SURVEY & REMONUMENTATION

APR 25 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
ONTONAGON **COMMISSION**  
(County)

Located In: \_\_\_\_\_ Corner Code #1 \_\_\_\_\_

1. Public Land Survey T 46N R 39W \_\_\_\_\_ G-4 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

APRIL 12 1994  
1105  
3  
*Richard L. Drahn* 187  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 1/4 Corner, Sections 9, 10; T46N., R39W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Drahn, in a field survey on June 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Zelotes B. Searls, U.S. Deputy Surveyor, on July 13, 1851.  
 Original bearing trees:

W. Birch	4"	S.65°E.	13 links	(8.58 feet)
W. Pine	30"	S.85°W.	16 links	(10.56 feet)

1933 C.C.C. Camp site plan for Camp Paulding shows quarter corner in center of old U.S. Highway 45 and on line with old road West.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Original corner and bearing tree destroyed by road construction. Corner found marked by a 1" diameter drill rod. No one knows who set this rod, but it is being used by the State Highway Department, Earl Applekamp (Land Surveyor), from Ewen, Michigan. Local residents all say this has been the corner for many years. Drill rod is in center line of old 45 and on line with old road West. I accepted drill rod as best representing the original corner location. Corner is also on line and midpoint between two N.W. and S.W. corners of Section 10.

**PEER GROUP Approved**

*Earl W. Applekamp* 04-07-94



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position I set a standard 2" diameter by 30" long split base aluminum monument with a 3 1/4" aluminum cap stamped to read: T46N., R39W.; 1/4; s.9, S.10; 1993; R.L.S. 21564: from which I established the following new blazed and scribed bearing trees and/or reference objects:

Wisconsin-Michigan Power Co. Pole #5888	S.12°E.	119.53 feet
Wisconsin-Michigan Power Co. Pole #74-0927	S.83°W.	31.09 feet

No other bearing objects close.  
 Monument was set over 1" drill rod.

A 6' steel sign post bears: S.58°E., 0.93 feet.

Signed by Richard L. Drahn Date February 10, 1994

Surveyor's Michigan License No. 21564

U.S.F.S. #G-13