

SURVEY & REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
ONTONAGON
(County)

Located In: _____ Corner Code #/ # _____
 1. Public Land Survey T 46N R 39W _____ K-4
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Recorded April 12 1995
 at 1:05 o'clock P. M. In
 Liber 3 page 190
Judith Boehm
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner, Sections 11, 12; T46N., R.39W.

I, Richard L. Drahn, in a field survey on July 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Zelotes B. Searls, U.S. Deputy Surveyor, on July 19, 1851. Original bearing trees:

Fir	6"	S.36°W.	15 links	(9.90 feet)
Sugar	18"	N.78°E.	8 links	(5.28 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing trees found. Corner re-established on line between the S.E. and the N.E. corners of Section 11

PEER GROUP Approved

Earl W. Applebaum 4-07-94
 Ont. Co. Rep

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a standard 2" diameter by 30" long split base aluminum monument with a 3 1/4" aluminum cap stamped to read: T46N., R.39W.; $\frac{1}{4}$; S. 11, S. 12; 1993; R.L.S. 21564; from which I established the following new blazed and scribed bearing trees and/or reference objects:

10"	Sugar Maple	N.74°W.	19.19 feet
12"	Sugar Maple	S.72°E.	21.18 feet
12"	Sugar Maple	S.45°W.	14.50 feet

A 6' steel sign post bears: N.52°W., 1.71 feet.



Signed by Richard L. Drahn Date February 10, 1995

Surveyor's Michigan License No. 21564
 U.S.F.S. G-21