

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>46N</u> R <u>39W</u> | <u>K-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded April 12 1994
 at 1:05 o'clock P M. in
 Lib. 3 page 191
Judith Boehm
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner, Sections 11, 12, 13, 14; T46N, R39W.

I, Richard L. Drahn, in a field survey on July 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Zelotes B. Searls, U.S. Deputy Surveyor, on July 19, 1851.
 Original bearing trees:

W. Pine	28"	S.41°W.	No distance
Sugar	18"	N75°E.	No distance

2" I.D. iron pipe set by G. G. Warrenner in 1931 bears N.87°E., 53.25 feet from the original corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at recorded bearings from the remains of the two original bearing trees. The first is a very large W. Pine stump at S.41°W., 21.6 feet with G.L.O. B.T. blaze. The second is now a large stump hole at N.75°E., 12.2 feet. Retracement distances north, south and west to natural features and recovered corners is consistent with the field notes of the original Government survey.

PEER GROUP Approved


Carl W. Gephke 4-07-94
 Ont Co Rep

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a standard 2" diameter by 30" long split base aluminum monument with a 3 1/4" aluminum cap stamped to read: T46N., R39W.; S.11, S.12, S.13, S.14; 1993; R.L.S. 21564: from which I established the following new blazed and scribed bearing trees and/or reference objects:

10"	Red Pine	N.88°W.	17.06 feet
12"	Red Pine	N.45°E.	5.92 feet
8"	Red Pine	S.11°W.	7.90 feet

A 6' steel sign post bears: S.45°E., 1.30 feet.



Signed by Richard L. Drahn Date February 10, 1994

Surveyor's Michigan License No. 21564

U.S.F.S. #J-21