

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R40W	I-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**SURVEY &  
 REMONUMENTATION**

MAY 22 1997

**COMMISSION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner common to Sections 26, 27, 34 & 35, T46N R40W.

I, Earl W. Applekamp, in a field survey on August 22 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, July 10, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Hemlock 10" S50°W 15.18 feet  
 Hemlock 20" N22°E 27.06 feet

PEER GROUP APPROVED  
Earl W. Applekamp  
 COUNTY REPRESENTATIVE 10-16-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found. Near the calculated position there were two trees blazed, 4 sides and painted blue. A blue line ran East from the calculated position. Timber was heavily cut South of this position. Corner was re-established at a position 1650 feet East of a ledge call. A GLO call North to the Scott & Howe Creek is in conformance. Distance from this corner to recorded North 1/4 corner and SE Corner is in agreement with original call. Based on evidence, corner was re-established at its original position.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" x 30" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, T46N R40W, S26, S27, S34, S35, 1996, P.S. 17610. I established the following bearing trees and reference object. Bearing and distance to tree are a nail.

11" Maple N27°-50'-19"W 15.51' - 8" Cherry S18°-01'-54"E 17.34'  
 9" Maple N70°-32'-01"E 22.29' - Steel Sign Post West 1.22'



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date October 2, 1996