

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon Located In: Corner Code #
 (County)

1. Public Land Survey T 47N R 38W F-5
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on September 3, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

(F-5) 1/4 Corner Common to Sections 9 & 16, T47N, R38W

A. Description of original monument and accessories and/or subsequent restoration:

1851 - Zelotes B. Searls set post.
 20" Hemlock S 30° W 10 links
 10" Cedar N 65° E 45 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original evidence and accessories were not recovered. This corner now falls in farming country. An old North-South fence and an old fence to the West now intersect at this corner. This fence intersection falls within 2 feet of a split of the distance between Section Corners. It is 30 feet South of a straight line between the Section Corners. This fence intersection has been accepted as the 1/4 corner by farmers for two generations and is the best remaining evidence of the original corner.

I have accepted the fence intersection as the 1/4 corner and have monumented it as such.

PEER GROUP APPROVED
Carl W. Applekamp
 COUNTY SURVEYOR 12-01-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 48" iron pin with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T. 47N, R. 38W; 1/4; S. 9, S. 16; 1997; P.S. 37273. Corner falls at intersection of fences to North, South, and West.

Witnesses:

4" Balsam S 21° E 9.26'
 11" Poplar S 34° W 14.41'
 6" Poplar N 56° W 17.08'
 4" Balsam N 01° W 9.90'
 Steel Sign Post East 0.50' (to face)
 NE Cor. Section 16 N 89° 19' 36" E 2643.95'
 NW Cor. Section 16 N 89° 19' 39" W 2638.80'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich Date 11/30/97
 Surveyor's Michigan License No. 37273

