

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 47N R 38W F-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on September 3, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

(F-7) 1/4 Corner Common to Sections 16 & 21, T47N, R38W

A. Description of original monument and accessories and/or subsequent restoration:

1851 - Zelotes B. Searis set post
 20" Y. Birch S 71° E 16 links
 18" Hemlock N 66° W 35 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories were not recovered. A North-South fence and a fence to the East intersect at this corner. American Can Corporation foresters have placed a yellow aluminum tag to the East indicating the fence intersection as the corner. This fence intersection falls 1.77 feet East and 0.93 feet South of a single prorated position. It has been accepted by surrounding property owners as the 1/4 Corner and is the best remaining evidence of the original 1/4 Corner.

I have accepted it as the 1/4 corner and have monumented it as such.

PEER GROUP APPROVED
Earl W. Applbaum
 COUNTY SURVEYOR
 12-01-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T. 47N, R. 38W; 1/4; S. 16, S. 21; 1997; P.S. 37273. The corner falls at the intersection of fences North, South and East.

Witnesses:
 6" Maple in clump N 15° W 5.04'
 6" Balsam N 65° E 11.65'
 16" Maple S 88° E 15.82' (American Can tag in tree)
 15" Maple S 20° W 13.02'
 Steel Sign Post West 1.98' (to face)
 SW Cor. Section 16 S 89° 44' 24" W 2640.84'
 SE Cor. Section 16 N 89° 41' 58" E 2637.30'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich Date 11/30/97
 Surveyor's Michigan License No. 37273

