

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 38W	G-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey September 3, 1995 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5											
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

(G-6) 1/4 Corner Common to Sections 16 & 15, T47N, R38W

A. Description of original monument and accessories and/or subsequent restoration:

1851 - Zelotes B. Searls set post
 20" Hemlock S 19° W 5 links
 10" Hemlock N 71° E 4 links

1964 - Michigan State Highway Department (M.S.H.D.) found a corner fencepost at this corner.

Fence Post North 31.81'
 Fence Post South 76.21'
 7" Maple N 85° W 10.71'

DEED GROUP APPROVED
Earl W. Applkamp
 COUNTY CLERK
 12-01-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories were not recovered. Corner now falls in a cleared field with remains of fences to the North, South, East, and West. I recovered remains of a corner fence post as called for by the M.S.H.D., but found none of their accessories. This corner fence post falls within 2.8 feet of the split of the distance between Section corners and 3.3 feet West of a line between them. It has been accepted by farmers on all sides as the 1/4 corner and is the best remaining evidence of the original corner.

I have accepted the remains of this corner fencepost as the 1/4 corner and have monumented it as such.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 48" iron pin with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T. 47N, R. 38W; 1/4; S. 16, S. 15; 1997; P.S. 37273.

Witnesses:

Wood Fence Post	East	9.94'
12" Apple Tree	S 32° W	15.25'
8" Soft Maple	N 86° W	76.28'
2" Sugar Plum	N 12° W	6.22'
Steel Sign Post	East	1.57' (to face)
NE Cor. Section 16	N 00° 06' 07" E	2631.60'
SE Cor. Section 16	S 00° 02' 35" E	2637.05'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 11/30/97

Surveyor's Michigan License No. 37273

