

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T47NR 39W	G-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

SURVEY &  
 REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Section Corner common to Sections 21, 22, 27 & 28, T47N R39W.

I, Earl W. Applekamp, in a field survey on April 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by E.B. Searls, U.S. Deputy Surveyor, June 5, 1851. ORIGINAL BEARING TREES: 24" Hemlock S27°E, 4 links, 12" Red Maple N21°W, 2 links. Corner restored by Donald D. Lappala (12585) on June 20, 1972 from Highway drawing and original field note calls. He set a 2"x5' long concrete filled galvanized iron pipe capped with a 3" stamped brass cap and the following new B.T.s: 9" Elm, N70°W, 47.4', 7" sugar maple S38°W, 99.7', 12" Elm, S65°W, 63.3' Center-line U.S.-45 West 75.8'. Corner recorded in Book 1 Land Corner, no page given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: \* established by Donald Lappala in 1972,

I found the 2"x5' long pipe completely destroyed by a cable laying machine. I restored the corner by using 2 of the bearing trees\* namely the 9" Elm, N70°W, 47.4', which is now just a 7' high stub and the 7" Sugar Maple S38°W, 99.7'. This tree is alive and in good shape. The 12" Elm has been destroyed by additional clearing for a transmission line.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp  
 COUNTY REPRESENTATIVE  
 5-11-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T47N R39W, S21, S22, S27, S28, 1999, P.S. 17610. I established two new bearing objects.

Nail in Power Pole	N03°W	109.70 feet
Nail in 10" S. Maple	N46°W	65.15 feet
6' Steel Sign Post	S45°W	3.7 feet



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date April 24, 1999