

# SURVEY & REMONUMENTATION

APR 25 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
ONTONAGON  
(County)

COMMISSION

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |              |              |       |       |
|------------------------------------|--------------|--------------|-------|-------|
| 1. Public Land Survey              | T <u>47N</u> | R <u>39W</u> | _____ | H-5   |
|                                    | T _____      | R _____      | _____ | _____ |
|                                    | T _____      | R _____      | _____ | _____ |
|                                    | T _____      | R _____      | _____ | _____ |
| 2. Property Controlling in Section | S _____      | T _____      | _____ | _____ |
|                                    | S _____      | T _____      | _____ | _____ |
| 3. Miscellaneous Property in Sec.  | S _____      | T _____      | _____ | _____ |
|                                    | S _____      | T _____      | _____ | _____ |

Recorded April 12 1995  
at 1:10 o'clock P. M. in  
Liber 3 Page 196  
*Judith A. Boehm*  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

¼ Corner, Sections 10, 15; T.47N., R.39W.

I, Richard L. Drahn in a field survey on June 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Zelotes B. Searls, U.S. Deputy Surveyor, on June 10, 1851.  
Original bearing trees:

Hemlock	6"	S.26°W.	10 links	( 6.60 feet)
Spruce	18"	N.30°E.	19 links	(12.54 feet)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

All original evidence destroyed by road construction. Re-established corner by single proportion measure on line between the N.E. and the N.W. corner of Section 15. Proportioned point falls on the center line of east and west county road and in line with old fence line north.

**PEER GROUP                      Approved**

*Earl W Applekamp 4-07-94*  
*Ont Co Rep.*



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position and 6" below surface of a east and west county road I set a 2" dia. by 12" long concrete-filled, galvanized iron pipe with a 3" brass cap stamped to read: T.47N., R.39W.; ¼; S.10, S.15; 1993; R.L.S. 21564. From which I established the following new, blazed and scribed bearing trees and/or reference objects:

Wisconsin electric power pole #37-25126	N.67°W.	82.48 feet
4" Red Maple	N.28°W.	71.26 feet
Wisconsin electric power pole #77-0466	N.81°E.	180.77 feet
A 6' steel sign post bears South 55.18 feet.		

A standard 30" long, aluminum reference monument with a 3¼" aluminum cap, stamped to indicate true corner position bears south, 54.31 feet.

Signed by Richard L. Drahn Date February 15, 1994

Surveyor's Michigan License No. 21564

U.S.F.S.                      J-15