

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 4/36 JEM Feet: 9.00
 96 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 47N R 40W T 48N R 40W	<u>T-1</u> ✓ T-13
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 2 & 3, T47N R40W and 34 & 35, T48N R40W.

I, Earl W. Applekamp, in a field survey on May 16, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by John Burt, U.S. Deputy Surveyor, July 13, 1850. Set Sugar Post.

ORIGINAL BEARING TREES:

Spruce 5" N07°E 28 links
 W. Pine 10" N55°W 25 links

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 07-08-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the apparent corner position there are fences running in all four directions. An old roadbed runs East for one mile. The location is in conformance with the original field notes. The corner was re-established using the evidence found at the site. The location of the section corners North, East and West were known and used to verify the location of this corner.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

AT the corner position I set a 2½"x30" aluminum pipe with a 3¼" cap stamped to read: County Remonumentation, T47N, T48N, R40W, S2, S3, S34, S35, 1996, P.S. 17610. I established three bearing trees and a reference object.

7" Oak S33°-37'-40"E 27.99' - 21" Oak N20°-44'-48"W 28.52'
 7" Aspen N58°-02'=07"E 39.30' - Steel Sign Post West 0.85'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 6, 1996